



A SILT FENCE

NOT TO SCALE

TEMPORARY VEGETATIVE SEEDING

(PRIOR TO ESTABLISHING PERMANENT VEGETATION)

AFTER COMPLETION OF GRADING ACTIVITIES AND THE CONSTRUCTION OF SWALES, ALL EXPOSED AREAS SHALL BE SEEDED TO THE FOLLOWING SPECIFICATIONS:

SEED BED

| | |
|-------------|--------------------|
| LIME | 1-1/2 TON PER ACRE |
| FERTILIZER | 1/2-TON PER ACRE |
| SEED | |
| RYE GRAIN | 50 LBS PER ACRE |
| TALL FESCUE | 100 LBS PER ACRE |

SUPPLEMENTAL SEED

MAY THROUGH AUGUST:

| | |
|----------|----------------|
| CENTPEDE | 5 LBS PER ACRE |
|----------|----------------|

PROCEDURE

STRAW MULCH SHALL BE APPLIED AT A RATE WHICH WILL INSURE APPROXIMATELY 75% COVERAGE OF THE SEEDED AREA. THE STRAW AND SOWN SEED WILL BE LIGHTLY DISCED INTO THE BED TO GIVE IT FURTHER RESISTANCE TO BLOWING AND WASHING. THE CONTRACTOR SHALL GUARANTEE A FULL STAND OF GRASS OVER THE ENTIRE DISTURBED AREA. IF NECESSARY THE CONTRACTOR WILL WET DOWN THE AREAS TO ASSIST IN SEED GERMINATION OR AID IN GROWTH IN TIMES OF EXCESSIVELY DRY WEATHER. A STAND OF GRASS WILL BE CONSIDERED ACCEPTABLE WHEN THE ENTIRE STAND OF GRASS IS AT LEAST FOUR INCHES HIGH AND HAS ACHIEVED AT LEAST 95% COVERAGE OF DISTURBED AREAS. RESEEDING WILL BE REQUIRED AS NECESSARY BY THE CONTRACTOR TO OBTAIN THE SPECIFIED STAND OF GRASS.

PERMANENT VEGETATION

ALL DISTURBED AREAS NOT COVERED WITH BUILDINGS, PAVEMENTS, OR OTHER IMPERMEABLE SURFACES SHALL BE SODDED WITH CENTPEDE SOLID SOD AS THE FINAL/PERMANENT VEGETATION.

REFERENCE SPECIFICATION SECTION 02 82 30 "RE-ESTABLISHING VEGETATION" FOR SPECIFIC SOD INSTALLATION AND SOD BED PREPARATION REQUIREMENTS.

SPECIAL SEEDING NOTE:

ALL DENUDED AREAS WILL, WITHIN 7 CALENDAR DAYS OF COMPLETION OF ANY PHASE OF GRADING OR CEASING OF GRADING ACTIVITIES, BE PLANTED AND PROVIDED WITH TEMPORARY OR PERMANENT GROUND COVER, DEVICES, OR STRUCTURES SUFFICIENT TO RESTRAIN EROSION.

ALL DENUDED AREAS WILL, WITHIN 7 DAYS OF COMPLETION OF CONSTRUCTION, BE PROVIDED PERMANENT GROUND COVER.

B VEGETATION PLAN

NOT TO SCALE

Digitally signed by John K Avolis



AVOLIS ENGINEERING, P.A.
P.O. BOX 15584
NEW BERN, NC 28561
PH: (252) 633-0068

LICENSE NO. C-0706



PANDA EXPRESS, INC.
1683 Walnut Grove Ave.
Rosemead, California
91770

Telephone: 626.799.9898
Facsimile: 626.372.8288

All ideas, designs, arrangement and plans indicated or represented by this drawing are the property of Panda Express Inc. and were created for use on this specific project. None of these ideas, designs, arrangements or plans may be used by or disclosed to any person, firm, or corporation without the written permission of Panda Express Inc.

REVISIONS:

| | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

ISSUE DATE:

| | | |
|---|----------------|------------|
| 1 | 95% SUBMITTAL | 03-21-2022 |
| 2 | 100% SUBMITTAL | 09-08-2022 |
| | | |
| | | |
| | | |
| | | |

DRAWN BY: STAFF

PANDA PROJECT #: D7898

ARCH PROJECT #: 01-2022

PANDA EXPRESS & HIBACHI-SAN

MCAS NEW RIVER
CURTIS RD & CAMPBELL ST
JACKSONVILLE, NC 28540

CG501

DETAILS

BID SET (04/10/2023) NOT FOR CONSTRUCTION